Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
129	Providing and laying in position reinforced cement concrete of Design mix M25 with OPC cement @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0.70 cum and fine aggregtes @ 0.47cum, with super plasticisers @ 3 liters confirming to is 9103-1999 reafirmed-2008 at machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation for footings, pedastals, retaining walls, return walls, walls (any thickness) including attached pilasters, columnspillars, posts, struts, buttresses, bed blocks, anchor blocks & plinths etc., including cost of all materials, labour, HOM of machinery, curing, complete but excluding cost of reinforcement as per specifications and directions of the Engineer in charge								
		Cum							
	Vivekananda Park								
	For Sump Bottam Slab		1	4.60	3.40	0.30	4.69		
	For Sump Side Wall		2	4.60	0.30	2.70	7.45		
			2	3.40	0.30	2.70	5.51		
	For Sump Top Slab		1	4.60	3.40	0.30	4.69		
	For Refilling Side Concrete		4	4.60	0.60	0.15	1.66		
	Nisargha Park								
	For Sump Bottam Slab		1	3.00	2.20	0.30	1.98		
	For Sump Side Wall		2	3.00	0.30	2.70	4.86		
			2	2.20	0.30	2.70	3.56		
	For Sump Top Slab		1	3.00	2.20	0.30	1.98		
	For Refilling Side Concrete		4	3.00	0.60	0.15	1.08		
	Toilet Area								
	Lintel		2	0.90	0.23	0.15	0.06		
	Slab		1	4.20	4.75	0.15	2.99		
							40.52		
					Upto 125%		**27.58**	**6222.33**	**171580.67**
					Above 125%		**12.94**	**6222.33**	**80,539.31**
	Approved Amount			**6222.33**					
130	Providing T.M.T bars Fe 500 steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications and directions of the Engineer in charge								
		Tmt							
	For Sump 100kg/Cum		1	37.46	100.00		3746.00		
	For Drain 90kg/Cum		1	26.00	100.00		2600.00		
	For Toilet 90kg/Cum		1	3.05	90.00		274.50		
							6620.50	Kg	
							6.62		
					Upto 125%		**4.15**	**75976.20**	**315301.23**
					Above 125%		**2.47**	**75976.20**	**187699.20**
	Approved Amount			**75976.20**					
131	Providing 20mm square M.S footrest and fixing in manhole Nos 232.00 with M 10 cement concrete block of 20x20x10cms, using 20mm and down size metal of size including cost of materials, labour charges, curing complete as per specifications and directions of the Engineer in charge								
		Nos							

Scanned by TapScanner

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
			4				4.00		
							4.00	**295.49**	**1,181.94**
	Approved Amount			**295.49**					
132	Waterproofing of RCC Terrace / podium slab / toilet / utilities / water retaining structure by preparing the surface by chipping and cleaning and Grouting of Honey comb, voids,cracks / construction joints with cement slurry (1kg cement added in 10 ltr of water) added with 100gm of inorganic accelerator, followed by spraying of liquid biological modified alkaline earth silicates @ 0.40 ltr per sqm on whole surface to reduce the micro porosity and allowing it to dry, curing the surface for the silicates to penetrate deeper into the concrete and spraying waterproofing impregnate liquid containing silane and silanol linear copolymer @ 0.50 ltr per sqm and finally applying polymer slurry made out of cross linked acrylic / styrene / butadiene & cement in the ratio of 1:0.1, @0.50kg/sqm on the whole surface, including all labour charges tools and equipments, all complete as per specifications and directions of the Engineer in charge								
		Sqm							
	Vivekananda Park								
	For Sump Bottam Slab		1	4.60	3.40		15.64		
	For Sump Side Wall		2	4.60		2.50	23.00		
			2	4.20		2.50	21.00		
	For Sump Top Slab		1	4.60	3.40		15.64		
	Nisargha Park								
	For Sump Bottam Slab		1	3.00	2.20		6.60		
	For Sump Side Wall		2	3.00		2.50	15.00		
			2	2.20		2.50	11.00		
	For Sump Top Slab		1	3.00	2.20		6.60		
							114.48	**563.14**	**64,467.76**
	Approved Amount			**563.14**					
133	Supply & fixing of Arm & Pedal Bike : All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out a minimum of 100 public park projects in India with EN16630-GS certified products either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory during technical bid. All products must clearly display the GS mark as has been issued in the								
		Each							
			1				1.00		
							1.00	**214625.00**	**214625.00**
	Approved Amount			**214625.00**					

Scanned by TapScanner

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
134	Supply & fixing of Big Shoulder Wheel : All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out a minimum of 100 public park projects in India with EN16630-GS certified products either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory during technical bid. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts								
		Each							
			1				1.00		151500.00
							1.00	**151500.00**	
	Approved Amount			**151500.00**					
135	Supply & fixing of Elliptical Cross Trainer: All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out a minimum of 100 public park projects in India with EN16630-GS certified products either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory during technical bid. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts are powder coated using AKZO Nobel - Great Wall Powder to the thickness of 80 - 120 microns. All metal parts are tested in our salt spray machine that uses a 5% NaCL solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. The seat and backrest is made from Rotomoulded LLDPE. Bearings : Maintenance-free ball bearings. Equipment which have sway and moving parts, must have built in limitors that prevent unwanted and ecesssive movement, which can cause injuries. The limitors must be in accordance with EN16630 safety norms. Scope of delivery : 1 completely pre-assembled equipment modules. Maintenance :								
		Each							
	Subhas Chandra Bose Road At RHS CC drain								
			15	0.28	0.30		1.27		
	Jyothi Nagara 2nd stage(Naidu Layout)								
			1			2.27	1.00		
							1.00	**176750.00**	**176750.00**
	Approved Amount			**176750.00**					

Scanned by TapScanner

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
136	Supply & fixing of Pull Down Challenger : All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out a minimum of 100 public park projects in India with EN16630-GS certified products either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory during technical bid. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts								
		Each							
			1				1.00		
							1.00	**298960.00**	**298960.00**
	Approved Amount			**298960.00**					
137	Supply & fixing of Seated Chest Press : All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out a minimum of 100 public park projects in India with EN16630-GS certified products either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory during technical bid. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts								
		Each							
			2				2.00		
							2.00	**290375.00**	**580750.00**
	Approved Amount			**290375.00**					
138	Supply & fixing of Rider : All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out a minimum of 100 public park projects in India with EN16630-GS certified products either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory during technical bid. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts are powder coated using AKZO Nobel - Great Wall Powder to the thickness of 80 - 120 microns. All metal parts are								
		Each							
			1				1.00		
							1.00	**113625.00**	**113625.00**

Scanned by TapScanner

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
	Approved Amount			113625.00					
139	Supply & fixing of Tai Chi Spinners : All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out a minimum of 100 public park projects in India with EN16630-GS certified products either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory during technical bid. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts are powder coated using AKZO Nobel Great Wall Powder to the thickness of 80 120 microns All metal								
		Each							
			2				2.00		
							2.00	**145187.50**	**290375.00**
	Approved Amount			**145187.50**					
140	Supply & fixing of HD Sit Up Station : All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out a minimum of 100 public park projects in India with EN16630-GS certified products either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory during technical bid. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc								
		Each							
			1				1.00		
							1.00	**157812.50**	**157812.50**
	Approved Amount			**157812.50**					
141	Supply & fixing of HD Squat Pushing : All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out a minimum of 100 public park projects in India with EN16630-GS certified products either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory during technical bid. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized								
		Each							
							0.00	**271437.50**	**0.00**
	Approved Amount			**271437.50**					

Scanned by TapScanner

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
142	Supply & fixing of HD Health Walker :All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out in excess of at least 50 public park projects in India either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts are powder coated using AKZO Nobel - Great Wall Powder to the thickness of 80 - 120 microns. All metal parts are tested in our salt spray machine that uses a 5% NaCL solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Footplates made of alloys of Nylon having good thermal stability. Internal Limited means no bump stops or crush points. Bearings : Maintenance-free ball bearings. Scope of delivery : 1 completely								
		Each							
			2				2.00		
							2.00	**176750.00**	**353500.00**
	Approved Amount			**176750.00**					
143	Supply & fixing of HD Mini Ski :All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out in excess of at least 50 public park projects in India either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts are powder coated using AKZO Nobel - Great Wall Powder to the thickness of 80 - 120 microns. All metal parts are tested in our salt spray machine that uses a								
		Each							
			1				1.00		
							1.00	**201091.00**	**201091.00**
	Approved Amount			**201091.00**					
144	Supply & fixing of HD Waist Twister :All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out in excess of at least 50 public park projects in India either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior								
		Each							

Scanned by TapScanner

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
			2						
							2.00		
	Approved Amount						**2.00**	**164125.08**	**328250.16**
	EIRL			**164125.08**					
E1	Providing and Fixing pre cast covering Slab 150mm thick made out of CC 1:2:4 and jelly 20mm Down size with steel reinforcement including form work,curing,including cost of alll materials, labour,hire charges of machinery, loading, unloading, lead and lift,transportation etc ,complete.As per Engineer incharge. (Data Rate)								
		Sqm							
	At Entrance gate								
	Ch:0.00m to 15.10m		1	15.10	0.90		13.59		
	Deduct Gratings		-1	2.80	0.60		-1.68		
	Ch:0.00m to 15.10m		1	15.40	1.20		18.48		
	Deduct Gratings		-1	2.80	0.60		-1.68		
							28.71	**2517.93**	**72,301.86**
	Data Rate			2493.00					
	Tender Premium 1%			24.93					
	Sub Total			**2517.93**					
E2	Providing and fixing in trenches galvanised / mild steel tubes (medium grade) 50mm dia nominal bore with all fittings (earth work in trenches to be measured and paid for separately) including cost of all materials, labour charges, HOM and testing complete as per								
		M							
	Vivekananda Park								
	Football		2	26.00			52.00		
							52.00	**423.23**	**22,007.98**
	Basic Rate			388.00					
	Area Weightage 8%			31.04					
	Sub Total			419.04					
	Tender Premium 1%			4.19					
	Total			**423.23**					
E3	KSRB 4.2.2 : Providing and laying in position reinforced cement concrete of Design Mix M20 with OPC @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregtes @ 0.460 cum, with super plasticisers @ 3 liters confirming to IS 9103-1999 reafirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation for footings, pedastals, retaining walls, return walls, walls (any thickness) including attached pilasters, columnspillars, posts, struts, buttresses, bed blocks, anchor blocks & plinths etc., including cost of all materials, labour, HOM curing,								
		Cum							
	Nisargha Park								
	New Drain Raft								
	Western Side								
			1	37.50	0.60	0.15	3.38		
	Eastern Side								
			1	41.00	0.60	0.15	3.69		
	New Drain Wall								
	Western Side								
			2	37.50	0.15	0.50	5.63		
	Eastern Side								
							12.69		

Scanned by TapScanner

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
	Ramp Concrete		2	41.00	0.13	0.50	6.15		
	At Northern Side gate								
	At Wester Side Gate		1	9.45	1.55	0.15	2.20		
	Middle of Ground		1	7.30	1.70	0.15	1.86		
	Deo Marvel Park		2	3.70	2.00	0.15	2.22		
	At Southern Side gate								
	For Plinth Concrete		1	6.20	7.00	0.15	6.51		
	Southern Side								
	Western Side		1	48.60	0.60	0.25	7.29		
	Northern Side		1	70.50	0.60	0.25	10.58		
	Gate-1		1	41.80	0.60	0.25	6.27		
	Gate-2		1	1.40	0.45	0.15	0.09		
	Gate-3		1	6.70	0.45	0.15	0.45		
	Gate-4		1	1.30	0.45	0.15	0.09		
	Gate-5		1	1.00	0.45	0.15	0.07		
	Deo Marvel Park		1	6.30	0.45	0.12	0.34		
	For Plinth Concrete								
	Eastern Side								
	Northern Side		1	52.30	0.55	0.15	4.31		
	Western Side		1	51.00	0.50	0.20	5.10		
	Southern Side		1	43.00	0.60	0.15	3.87		
			1	36.50	0.60	0.15	3.29		
							73.40	**6172.84**	**453086.25**
	Basic Rate			5659.00					
	Area Weightage 8%			452.72					
	Sub Total			6111.72					
	Tender Premium 1%			61.12					
	Total			**6172.84**					
E4	Providing and fixing M.S. Grill over existing compound wall as per using 16mm x 16mm M.S. Square rod at 150mm c/c spacing and 6mm x 40mm M.S. flats at horizontal and 6mm x12mm M.S. flat for ornamental design and providing shop edge design at the vertex of every vertical rods, including welding, grinding wherever necessary. All the steel surface								
		Sqm							
	Nisargha Park								
	Eastern Side								
			1	78.00		1.20	93.60		
							93.60	**5422.69**	**507563.78**
	Basic Rate			5369.00					

Scanned by TapScanner

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
	Tender Premium 1%			53.69					
	Total			**5422.69**					
E5	Supply & fixing of Bicycle : All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out a minimum of 100 public park projects in India with EN16630-GS certified products either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory during technical bid. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are								
		Each							
			2				2.00		
							2.00	**157812.50**	**315625.00**
	Data Rate			**156250.00**					
	Tender Premium 1%			1562.50					
	Sub Total			**157812.50**					
E6	Supply & fixing of Self Weight Rower: All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out a minimum of 100 public park projects in India with EN16630-GS certified products either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory during technical bid. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts								
		Each							
			1				1.00		
							1.00	**208312.50**	**208312.50**
	Data Rate			**206250.00**					
	Tender Premium 1%			2062.50					
	Sub Total			**208312.50**					
								Total Construction Cost	**50003072.95**

Assistant Engineer
Yelahanka Project Division
BBMP Bangalore

Asst. Executive Engineer
Yelahanka Project Division
BBMP Bangalore

Executive Engineer
Yelahanka Project Division
BBMP Bangalore

Technical Sanction
Accorded For Rs. 50003072.95
Head of A/C P.3.748 ....
CER NO :..124..... Dt:..06.06.2022

Scanned by TapScanner